

BILL NO. 3: PLATFORM CASTING AND PUMP INSTALLTION

Item	Description	Unit	Qty	Rate	Amount
				(Ushs)	(Ushs)
3.1	Construction of hand pump platform (in reinforced concrete mix 1:2:4- reinforced with welded mesh , drainage channel reinforced with 10mm diameter bar), including installation of pedestal as design drawing and Cosnrtction of soak away pit (1.5m diameter and 1.5m deep, filled with hardcore)	No.	1		0
3.2	Supply and installation of U2 pump complete with U2 cylinder-complete, stainless steel (ss) riser pipes (Minimum of 10 pipes per borehole), ss connecting rods - 3m long (Minim of 10 number per borehoels) and head assembly (completed). The ss pipe should comply to the following specification: 32mm or 1 1/4" ss riser pipes in 3m length with O ring and a welded seamless socket in AISI304. 1 piece of nipple addaptor stainless steel AISI 316)	No	1		0
	Total of Bill No3 carried to Summary				0